Onslow Water Supply: Shire of Ashburton

NOTICE OF PROPOSAL TO CONSTRUCT ONSLOW SEAWATER DESALINATION PLANT

Water Corporation proposes to construct the Onslow Seawater Desalination Plant. Commencement of the works described on this Notice of Proposal is conditional upon obtaining all necessary project approvals.

The Onslow Desalination Plant will provide an additional water source to meet demand in the town of Onslow due to growth and development.

The proposal includes the construction of a new 1.5 ML/day desalination plant and associated infrastructure that can be expanded to an additional 0.5 ML/day

with further investment. The scope of works include: Reverse osmosis desalination plant (700 metres long) in Beadon Bay • 1 ML clearwater storage tank Site access road water tanks Manager, Mr Andre Azis, on 0448 776 308. the instructions in the accompanying letter. 1 ML CLEARWATER -STORAGE TANK **LEGEND** PROPOSED WATER PIPE *303* EXMOUTH : PROPOSED WASTEWATER PIPE PROPOSED REVERSE OSMOSIS EXISTING WATER PIPE DESALINATION PLANT EXISTING PRESSURE MAIN EXISTING SEWER LINE EXISTING WATER TANKS EXISTING CADASTRAL BOUNDARY LOT 552 PROPOSED DESALINATION PLANT NINGALOO -200mm DIAMETER **DETENSION** WATER PIPELINE EXISTING WATER PUMP STATION **STORMWATER** LOT 551 EXISTING WASTEWATER TREATMENT PLANT - SITE ACCESS ROAD DESALINATION PLANT INSERT N: 7604141.00 **PLAN** SCALE: DIAGRAMMATIC RECOMMENDED NORTH POINT 20/03/2024 ONSLOW WATER SUPPLY DES CALC AHD . BURAK I. BURAK COORDINATE SYS | DES CHD PREREQUISITES TO WORKS PRINCIPAL ENGINEER, TREATMENT DESIGN **ENGINEERING** MGA94-50 A. AZIS 20/03/2024 ASCON SURVEY

- Two marine pipelines for intake of water (400 metres long) and one outfall
- Plant stormwater basin and stormwater detension basin
- 2.5km of below ground 200mm diameter water pipeline to the existing
- Belowground wastewater pipeline connecting to the existing sewer line

The location of the proposed works are shown on the Locality Plan. Works will occur on Crown Land Lots 551, 552 and 354, between Bindi Bindi Aboriginal Community and Discovery Parks Onslow. Lot 553 will be utilised as a temporary lay down area. Works will also occur in the McAullay Road reserve and the Beadon Creek road reserve. The proposed works are scheduled to commence in 2024 and will continue for a duration of approximately 18 months.

Further project information may also be obtained by contacting the Project

Objections to the proposed works will be considered if lodged in writing as per

ONSLOW WATER TREATMENT PLANT NOTICE OF PROPOSAL — GENERAL WORKS

CAD ISSUE LJ23-0-2 CAD MANAGEMENT_NOT READ ONLY\WT\NWR\ONSLOW\DESAL PLANT\CAD\LJ23-000-002-01A 14:21 24/04/2024 DRUCEJ2/NB46087

LOCALITY PLAN

NOT TO SCALE

SHEET

100500 100 200 300 400 500 600 700 m

LOCATION OF WORKS -

PEEDAMULLA -

J. DRUCE

Q.C. CHD

NONE

NONE

DRN | REC | APPD

SSUE DATE GRID

B. MOULDS

SENIOR PRINCIPAL ENGINEER, WT